KEYSTONE ACCESSIBILITY

717 219 7976
FAX: 717 539 4536
INFO@KEYSTONEACCESSIBILITY.COM
WWW.KEYSTONEACCESSIBILITY.COM

WORK BY OTHERS – POLLOCK ELEVATOR

The following work is to be completed by others prior to the installation of the Pollock elevator. All work must be carried out to the highest standards of construction and in accordance with the project drawings and cut sheets.

- Electrical Requirements
  A dedicated 120V outlet must be provided near the motor in close proximity to where the rails will be installed, as indicated on the shop drawings. The outlet should be on its own circuit and ready for use prior to installation.

- Phone Line
  A phone line is required by code and should be installed to the location behind or near the motor, with enough slack to connect directly to the controller. If a landline is not available, we can provide a cellular adapter with a battery backup and sim card for an additional cost that can be mounted on the wall near the motor.

- Floor Aperture Preparation
  The floor opening (aperture) must be cut and reframed to the exact dimensions specified on the Pollock cut sheet. The opening must be square with the rear wall and square with itself. Proper care must be taken to ensure accuracy in dimensions, plumb, and level framing.

- Finishing of Aperture
  The top and bottom of the floor opening must be finished by others if necessary. The inside surfaces of the aperture should remain exposed with rough 2x10 framing (wood for framing can vary and is project specific), as Keystone Accessibility will provide and install finishing materials on the inside surfaces as part of the elevator system.